BRUHAT BANGALORE MAHANAGARA PALIKE

Item No.62

APPROVED SCHEDULE - B

Tender Notification No: BBMP/ EE /Btp/Ten/05/2012-13 Dated: 30-07-2012

Name of Work: Improvements to Roads and Drains in Hosabalunagara and Singapura Garden in Ward No. 11 Kuvempunagara.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SUBBANNA	
				In Figures	In Words
1	307.80	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. **Page No. 149/ Item No. 19.1/ PWD SR 2011-12**	Cum	60.97	Rupees Sixty and Ninety Seven Paise Only
2	134.80	KSRRB 300-2 : Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3 **Page No. 149 / Item No. 19.2/ PWD SR 2011-12**	Cum	84.44	Rupees Eighty Four and Forty Four Paise Only
3	182.25	Removing B.S. Slab Drain and stacking (P.28/I.5.32 PWD SR - 2011-12)	Sqm	46.09	Rupees Forty Six and Nine Paise Only
4	182.25	Refixing stone slabs of drains and pointing in CM (1:3) (P.28/I.5.33 PWD SR - 2011-12)	Sqm	58.37	Rupees Fifty Eight and Thirty Seven Paise Only
5	144.00	Providing **7.5 cms thick** granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete (P.28/I.5.31.1 PWD SR - 2011-12)	Sqm	322.40	Rupees Three Hundred Twenty Two and Forty Paise Only
6	192.38	KSRRB M300-53. Construction of embankment with approved materials Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications. which includes cost of gravel / Murrum, watering charges & compaction by vibratory roller) **PWD SR 2011-2012 Bangalore circle Pg No. 156, I No. 19.60**	Cum	142.47	Rupees One Hundred Forty Two and Forty Seven Paise Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SUBBANNA	
				In Figures	In Words
7	5.94	KSRB 4-1.3 : Providing and laying in position **plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs** using 40mm and down size graded granite metal, corse aggregates @ 0.85 cum and fine aggregtes @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.12/I.4.3 PWD SR - 2011-12)	Cum	3821.23	Rupees Three Thousand Eight Hundred Twenty One and Twenty Three Paise Only
8	15.84	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation **cement mortar 1:6**, stone hammered dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specification. KBS 5.1.13 (P.25/I.5.6 PWD SR - 2011-12)	Sqm	2743.03	Rupees Two Thousand Seven Hundred Forty Three and Three Paise Only
9	2.64	KSRB 4-1.6 : Providing and laying in position plain cement concrete of **mix M15 with cement @ 240 kgs with 20mm** and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1,4.2. **No. 12/ Item No. 4.6/ PWD SR 2011-12**	Cum	4328.47	Rupees Four Thousand Three Hundred Twenty Eight and Forty Seven Paise Only
10	26.40	KSRB 15.1.1 Providing flush pointing to square rubble, course or uncoursed stone masonry with **cement mortar 1:3,** 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. (P.119 / I.15.1 PWD SR - 2011-12)	Sqm	73.56	Rupees Seventy Three and Fifty Six Paise Only
11	79.04	KSRB 4-6.4: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (P.17 / I.4.31 PWD SR - 2011-12)	Sqm	214.76	Rupees Two Hundred Fourteen and Seventy Six Paise Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SUBBANNA	
				In Figures	In Words
12	8.94	KSRB 4.2.2 : Providing and laying in position **reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm** and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459 cum wuth superplastisier @ 3lts confirming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, wall (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.6 **(P.13/I.4.11 PWD SR - 2011-12)**	Cum	5137.85	Rupees Five Thousand One Hundred Thirty Seven and Eighty Five Paise Only
13	7.60	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 **Page No. 19/ Item No. 4.46/ PWD SR 2011-12**	Qtl	7127.39	Rupees Seven Thousand One Hundred Twenty Seven and Thirty Nine Paise Only
14	192.38	Providing, laying, spreading and compacting graded stone aggregate to **wet mix macadam** specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications **(P.166/I.20.18) PWD SR - 2011-12.**	Cum	1028.74	Rupees One Thousand Twenty Eight and Seventy Four Paise Only
15	1282.50	KSRRB 500-1.1 : Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing complete as per specifications. Specification No. 500-1.3 **(P.171/I.21.1) PWDSR 2011-12**	Sqm	9.74	Rupees Nine and Seventy Four Paise Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P,
Bangalore - 560 092

Sl. No	Approved Qty.	Description	Unit	Approved Tender Rates of SUBBANNA	
				In Figures	In Words
16	1282.50	KSRRB M500-6: Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. MORTH specification NO. 502, **Page No. 171/ Item No. 21.6/ PWD SR 20011-12 Revised Rate**	Sqm	39.37	Rupees Thirty Nine and Thirty Seven Paise Only
17	32.06	KSRRB M500-18: Providing and laying **semi dense bituminous concrete** 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications. **With 80/100 grade bitumen, No. 151/ Item No. 21.20.1/ PWD SR 2011-12 Revised Rate**	Cum	8615.85	Rupees Eight Thousand Six Hundred Fifteen and Eighty Five Paise Only
18	442.60	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123) Basic rate for haulage of materials as per item no.17.4 page 141) Rs. 2.00	Cum	70.53	Rupees Seventy and Fifty Three Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92